

e-NG Plants



e-NG Plants Operations and Maintenance Cost Risk for First Time Operators

Gulf LNG Solutions Technical Report Series | Energy and Process Technology Analysis

A technical risk and readiness guide for project developers, owners, operators, lenders, and EPC teams. September 2026.

e-NG, also called e-methane or synthetic methane, is made by combining low-carbon hydrogen with a qualified carbon-dioxide source and conditioning the product for pipeline injection, liquefaction, storage, or end use.

For Gulf LNG Solutions energy and process technology portfolio resources, visit www.GulfLNGSolutions.com or contact Info@GulfLNGSolutions.com

Disclaimer

This technical document has been prepared by Gulf LNG Solutions for general information and discussion. It is based on publicly available information and professional engineering judgment. It does not constitute engineering design, an operating procedure, legal advice, investment advice, regulatory approval, or a warranty of project performance.

e-NG facilities handle hydrogen, carbon dioxide, methane, high-pressure equipment, electrical systems, and where applicable cryogenic LNG systems. Owners and operators must obtain qualified, project-specific engineering, process-safety, environmental, legal, insurance, and regulatory advice before making decisions or undertaking any operating activity. Applicable laws, codes, standards, permits, equipment manuals, and site conditions govern each project.

Performance, availability, cost, schedule, utility consumption, carbon-intensity, and emissions outcomes depend on the selected technology, configuration, operating conditions, commercial agreements, supply chain, workforce, and local requirements. Gulf LNG Solutions disclaims responsibility for decisions made solely in reliance on this document.

Page Index and Contents

Executive Summary..... 3

Part I Operations and Maintenance (O&M) Cost Risk Analysis.....5

1 Scope and Operating Context..... 5

2 e-NG Process Configuration and Interfaces..... 5

3 O M Cost Structure and Risk Mechanisms..... 6

4 Major Risk Areas..... 7

5 Risk Register for First Time Operators..... 8

6 O M Readiness Model..... 9

7 Contracting and Commercial Protections..... 10

8 Financial Modeling Guidance..... 11

9 Due Diligence Questions for Owners and Lenders..... 11

10 Recommended 90 Day Mobilization Plan..... 12

Part II Decision Toolkit Cards..... 13

Decision Toolkit Cards 01 through 90..... 13

Part III e-NG Plant Technical Commercial Market and Execution Compendium..... 105

11 e-NG Technology Commercial and Market Background..... 105

12 e-NG Technical Decision Toolkit..... 113

13 e-NG and Ethylene Plant Methanation Comparison..... 119

14 Illustrative United States e-NG Development Case..... 121

15 e-NG as a Hydrogen Carrier..... 124

16 Global e-NG Investment Justification and Risk Analysis..... 126

17 Hydrogen Electrolysis Design Economics and Safety for e-NG Facilities..... 130

18 EPC Execution Critical Path and Design Challenges..... 137

19 Owner EPC Technology Licensor and Procurement Planning..... 140

20 United States Benchmark and China e-NG Development Case..... 142

21 Process Safety Refresher for EPC and Owner Teams..... 145

Part IV Appendices..... 147

Appendix A Reference Frameworks..... 147

Appendix B Public Reference Notes..... 147

Gulf LNG Solutions Support and Disclaimer..... 148

Executive Summary

The principal O&M risk in e-NG is not the methanation reactor alone. It is the integrated operating chain: electricity and electrolyzer behavior; water quality; CO2 source continuity and contaminant control; hydrogen and CO2 compression; methanation reaction and heat removal; gas purification and specification management; product storage, pipeline or LNG interface; and carbon-accounting evidence. A first-time operator must run all of these systems as one facility while establishing new procedures, maintenance routines, data governance, and commercial interfaces.

The most common base-case omission is the cost of imperfect integration. Intermittent power can reduce electrolyzer utilization; variable CO2 composition can contaminate catalysts or trigger purification load; product specification or certificate failure can strand inventory; and a small common utility upset can idle the whole chain. The corresponding controls must be designed into FEED and procurement, rather than left to a post-startup operating team.

Decision Toolkit Cards. 1 through 90 are the report’s implementation layer. They convert the technical discussion into controlled project decisions spanning development, FEED, procurement, construction, commissioning and first-year operation. Each retained card should identify a decision owner, the evidence required, the downside case, the approval gate and the resulting operating or commercial consequence before capital is committed or the facility is started.

The cards are organized around ten core subject archetypes—power and CO2 integration, operating readiness, availability, certificate revenue, maintainability, methanation control, critical spares, data rights, CO2 change management and off-spec inventory. Cards 11 through 90 repeat those archetypes so a real project can allocate them by train, equipment package, supplier, operating phase or contract. They are not 90 completed diligence findings: repeated evidence, red-flag and O&M-cost prompts are open templates until replaced by asset-specific evidence, quantified exposure and an accountable closure action. Owners should remove non-applicable duplicates or consolidate them into a controlled live register; EPC, OEM and operations teams should populate the retained cards with the relevant tag, document, guarantee, test result, cost/availability impact and due date.

Part III Compendium. Part III is the report’s practical, comprehensive e-NG reference for owners and developers, operators and maintainers, process and project engineers, EPC and EPCM teams, technology licensors and OEMs, lenders, investors, insurers, commercial teams and independent reviewers. Chapters 11 through 21 bring together the technical, commercial, market and execution

subjects that a card alone cannot explain: CO2 sourcing and qualification, hydrogen routes and electrolysis, methanation and catalyst operation, TIC and scale economics, product/export interfaces, U.S. and China market logic, EPC procurement and critical path, and process-safety readiness. It should be used alongside the Toolkit to turn each project decision into an evidence-based, designable and operable action.

Priority risk	Why it matters	Control
Availability and integration	One constraint can stop e-NG production	Transparent RAM model and operating-envelope tests
CO2 quality and provenance	Contaminants and ineligible carbon can damage value	Specification, analyzers, guard beds, audit trail
Hydrogen cycling	Dispatch affects efficiency and stack life	Duty-cycle warranty, buffer strategy, stack renewal plan
Methanation heat management	Exotherm and recycle behavior affect catalyst and safety	Dynamic control review, hot-spot monitoring, trained operators
Product specification	Water, CO2, H2, O2 or inert limits can constrain delivery	Online quality monitoring and segregation plan
Certificates and carbon intensity	A molecule may be saleable but not qualify as e-NG	Data architecture, mass balance and independent assurance